

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Osborne County, Sec. 18 Twp. 10S Rge. 15W 1/4/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SE/4 SE/4 SW/4

Lease Owner Harold Krueger Et al
Lease Name Locke Well No. 1

Office Address Natoma, Kansas 67651
Character of Well (Completed as Oil, Gas or Dry Hole) D & A

Date Well completed July 30, 1978
Application for plugging filed July 30, 1978
Application for plugging approved July 30, 1978
Plugging commenced July 30, 1978
Plugging completed July 30, 1978

Reason for abandonment of well or producing formation D & A


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane L. Rankin

Producing formation Depth to top Bottom Total Depth of Well 13,085'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	290.64'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged w/50 sx cement @ 550'
25 sx cement @ 300'
1 sx hulls & plug @ 40' w/10 sx to bottom of cellar
Cement was 50-50 Pozmix, 4% Gel

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1978
8-10-78
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
1720 KSB&T Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick, ss. contractor
Gloria Fawcett (employee of ~~xxxxxxx~~)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 KSB&T Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of August, 1978.

Joyce A. Hagermann
Notary Public.

My commission expires



DRILLERS LOG

No. 1 Locke

CASING RECORD:	COMPANY: Harold Krueger Et al	DESCRIPTION:
8 5/8" @ 298' w/210 sx cement	CONTRACTOR: Red Tiger Drilling Company	C SE/4 SE/4 SW/4 Sec. 18-T10S-R15W Osborne County, Kansas
	COMMENCED: July 25, 1978	
	COMPLETED: July 30, 1978	
TOTAL DEPTH: 3,085'		ELEVATION: 2,021' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock	0	29	
Rock	29	41	
Shale	41	545	
Shale & Sand Streaks	545	900	
Shale	900	1205	
Anhydrite	1205	1242	
Shale	1242	1775	
Shale & Lime	1775	2360	
Lime & Shale	2360	2500	
Shale & Lime	2500	2625	
Lime & Shale	2625	3032	
Lime	3032	3085	
RTD		3085	

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1978
8-10-78
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 1st day of August, 1978.

Joyce A. Hagermann
Notary Public

