

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05802-00-01  
Spot: SESWNE Sec/Twnshp/Rge: 21-11S-18W  
2970 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: WASINGER Well #: 11  
County: ELLIS Total Vertical Depth: 3603 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 8223 WILLOW PLACE SOUTH  
HOUSTON, TX 77070

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3600	0	250 SX
SURF	10.75	1338	0	550 SX

\$ 117.10

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/22/2006 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS CORPORATI Phone: (281) 517-7199

Proposed Plugging Method: Ordered out 500 sxs 60/40 pozmix - 10% gel - 20 sxs gel.  
Holes in casing from 500' - 650'. TOF 2915'.  
Left in the hole 17 joints 2 3/8" and AD-1 packer.  
Note: Per letter in UIC file from Citation Oil and Gas, this well was recompleted and injection began August 31, 1963.  
Well was never added to Docket E-15856.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/22/2006 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 2910' - mixed and spotted 20 sxs cement.  
Pulled up to 2700' - pumped 20 sxs gel spacer.  
POOH. Perforated casing at 1350'.  
TIH with tubing to 1350' - circulated cement up 7" and 10 3/4" with 380 sxs.  
POOH. Topped with 15 sxs.

Perfs:

Top	Bot	Thru	Comments
3324	3386		LANSING KC
3051	3206		TOPEKA

INVOICED

DATE 12-1-06  
INV. NO. 2007060888

Remarks: LEASE ORIGINALLY KNOWN AS WASINGER B-1. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

110

Signed

(TECHNICIAN)

NOV 29 2006

RECEIVED Form CP-2/3

NOV 30 2006

KCC WICHITA

PKT

MID STATES OIL CORP

#1 WASINGER B

21-11-18W

SE SW NE

Contr.

ELLIS

County

E 2062

Comm. 4-19-48


Comp. 5-21-48

IP 282 BOPD PHY POT

Tops	Depth	Datum
ANH	1331	+731
TOP	3017	+955
LANS	3288	-1226
ARB	3598	-1536
T.D.	3603	

Casing

10" 1338 1900' 01H/19 HRS  
 7" 3598 SWB 30 BOPH/3 HRS  
 ACID 500  
 SWB 147 BO/4 HRS



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS