

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-19000-00-01  
Spot: W2SENE Sec/Twnshp/Rge: 26-17S-25W  
3300 feet from S Section Line, 990 feet from E Section Line  
Lease Name: ROSS A POTTER Well #: 4  
County: NESS Total Vertical Depth: 4425 feet

Operator License No.: 5363

Op Name: BEREXCO, INC.

Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4424		175 SX
SURF	8.625	250		150 SX

**\$ 143.81**

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/27/2006 12:05 PM

Plug Co. License No.: 32810

Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC

Proposal Rcvd. from: MARK LEIKER

Company:

Phone: (785) 628-6101

Proposed Plugging Method: TUBING & RODS ARE SANDED IN HOLE FROM 1120' TO BOTTOM-TRIED FOR 3-DAYS TO GET OUT OF HOLE COULD NOT. RUN TUBING TO 1120' AND MIX 110 SX CMT AND 300# HULLS AND CMT. CIRCULATED TO SURFACE, PULLED CASING AND TOPPED OFF WITH 15 SXS CMT, TIED ONTO BACKSIDE AND PUMPED 5 SXS CMT AND PRESSURED TO 500 # AND HELD.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/27/2006 1:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TUBING & RODS ARE SANDED IN HOLE FROM 1120' TO BOTTOM-TRIED FOR 3-DAYS TO GET OUT OF HOLE COULD NOT. RUN TUBING TO 1120' AND MIX 110 SX CMT AND 300# HULLS AND CMT. CIRCULATED TO SURFACE, PULLED CASING AND TOPPED OFF WITH 15 SXS CMT, TIED ONTO BACKSIDE AND PUMPED 5 SXS CMT AND PRESSURED TO 500 # AND HELD.

Perfs:


Top	Bot	Thru	Comments
4402	4418		MISS
4390	4396		MISS
4312	4317		FT. SCOTT
4295	4307		FT. SCOTT
3192	3221		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED

Plugged through: TBG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 29 2006

KCC WICHITA

*PRY*