

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-005-20117-00-00
Spot: SENWNESE Sec/Twnshp/Rge: 11-7S-20E
2100 feet from S Section Line, 700 feet from E Section Line
Lease Name: EMZEN Well #: 43-11
County: ATCHISON Total Vertical Depth: 1710 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1695	0	327 SX
SURF	8.625	40	0	65 SX

\$ 55.58

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/16/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1647' TO 1613' CEMENT FROM 1613' TO 1337' GEL FROM 1337' TO 175'. CWMWNT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 03/16/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 1640' and pumped 10.25 barrels of gel. Gel was placed from 1640' to 1610'. Pulled the tubing up to 1610' and pumped 16.5 barrels of gel and 30 sacks of cement with 1 sack of cottonseed hulls. The cement was placed from 1610' to 1337' and gel from 1337' to 274'. Pulled the tubing up to 274' and circulated 30 sacks of cement from 274' to surface.

Perfs:

Top	Bot	Thru	Comments
1561	1563		
1518	1521		
1475	1477		
1460	1463		
1387	1389		

RECEIVED
KCC DISTRICT #3

NOV 20 2006

CHANUTE, KS

TH

INVOICED

DATE 12-4-06
INV. NO. 2007060898

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

RECEIVED
NOV 27 2006
KCC WICHITA

Form CP-2/3

Plg