

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21352-00-00  
Spot: SESE Sec/Twnshp/Rge: 6-24S-17W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: CROSS Well #: 2-6  
County: EDWARDS Total Vertical Depth: 4546 feet

Operator License No.: 5056  
Op Name: HOLL, F.G., COMPANY L.L.C.  
Address: 9431 E CENTRAL, SUITE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4501	2060	225 SX
SURF	8.625	319		225 SX

**\$ 147.75**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: MR. ROB LONG Company: \_\_\_\_\_ Phone: (620) 793-0915

Proposed Plugging Method: SAND TO 4300' WITH 4 SX CMT. 1ST PLUG AT 1200' WITH 15 SX GEL AND 50 SX CMT. FLUID TO SURFACE. 2ND PLUG AT 600' WITH 40 SX CMT. FLUID TO SURFACE. 3RD PLUG AT 330' WITH 40 SX CMT. FLUID TO SSURFACE. 4TH PLUG AT 40' WITH 10 SX CMT. CMT TO SURFACE

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/07/2006 11:00 AM KCC Agent: JERRY W. STAPLETON

**Actual Plugging Report:**

SAND TO 4300' WITH 4 SX CMT. 1ST PLUG AT 1200' WITH 15 SX GEL AND 50 SX CMT. FLUID TO SURFACE. 2ND PLUG AT 600' WITH 40 SX CMT. FLUID TO SURFACE. 3RD PLUG AT 330' WITH 40 SX CMT. FLUID TO SSURFACE. 4TH PLUG AT 40' WITH 10 SX CMT. CMT TO SURFACE

**Perfs:**

Top	Bot	Thru	Comments
4371	4378		
4353	4362		

**INVOICED**

DATE 12-4-06  
INV. NO. 2007060899

Remarks: 60/40 POZMIX 6% GEL BY COPELAND CEMENT RECOVERED 2060' OF 4 1/2" CASING

Plugged through: CSG

District: 01

Signed Jerry W. Stapleton  
PART II (TECHNICIAN)

RECEIVED Form CP-2/3

NOV 29 2006

KCC WICHITA

*PKT*