

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22127-00-01
Spot: S2S2NW Sec/Twnshp/Rge: 16-30S-14W
2332 feet from N Section Line, 1479 feet from W Section Line
Lease Name: STANNARD B Well #: 1-16
County: BARBER Total Vertical Depth: 4740 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	1820	4200		325 SX CMT.
SURF	8.625	326		250 SX

\$ 154.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2006 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: STEVE BODINE Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 793-2757

Proposed Plugging Method: SANDED TO 3230' WITH 4 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. FLUID TO SURFACE. 2ND PLUG AT 360' WITH 50 SX CMT. FLUID TO SURFACE. 3RD PLUG AT 40' WITH 10 SX CMT. CEMENT TO CIRCULATE TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2006 4:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SANDED TO 3230' WITH 4 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. FLUID TO SURFACE. 2ND PLUG AT 360' WITH 50 SX CMT. FLUID TO SURFACE. 3RD PLUG AT 40' WITH 10 SX CMT. CEMENT TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4586	4589		
4221	4225		
3278	3282		

INVOICED

DATE 12-4-06
INV. NO. 2007060894

Remarks: USED 60/40 POZMIX 6% GEL. RECOVERED 1820 OF 41/2" CASING

Plugged through: CSG

District: 01

Signed

Jerry W. Stapleton
PART II
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 29 2006
KCC WICHITA

PT