

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-26721-00-00
Spot: N2NWNENW Sec/Twnshp/Rge: 9-34S-11E
5050 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SNELL Well #: 25
County: CHAUTAUQUA Total Vertical Depth: 1316 feet

Operator License No.: 31590

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40	0	

Op Name: ELWELL, MIKE

\$ 42.77

Address: 1648 CRESCENT RD.
LAWRENCE, KS 66044

Well Type: OIL DH *per 2/3 ap* UIC Docket No: _____ Date/Time to Plug: 09/05/2006 8:00 AM

Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed Plugging Method: TO PUMP CEMENT & GEL TO FILL WELL.

Plugging Proposal Received By: RON ROWE WitnessType: NONE
Date/Time Plugging Completed: 09/05/2006 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

Perfs:

RAN 1" TUBING INSIDE 8.6250" SURFACE PIPE & OPEN HOLE TO 1300', GELLED HOLE & PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" OUT & TOPPED-OFF WELL. USED TOTAL OF 95 SACKS CEMENT * 2 SACKS GEL.

RECEIVED
KCC DISTRICT #3

NOV 5 2006 RR

CHANUTE, KS

INVOICED
DATE: 12-4-06
INV. NO: 2007060897

Remarks: PLUGGED DRY HOLE.

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)

RECEIVED
NOV 27 2006
KCC WICHITA

PKT