

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-005-20116-00-00  
Spot: E2W2SWSE Sec/Twnshp/Rge: 5-7S-21E  
622 feet from S Section Line, 2154 feet from E Section Line  
Lease Name: WALNUT Well #: 5-1 SWD  
County: ATCHISON Total Vertical Depth: 2426 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5	2048		
PROD	7	1918	0	203 SX CMT
SURF	9.625	225	0	140 SX CMT

\$ 78.85

Well Type: SWD UIC Docket No: D28133.0 Date/Time to Plug: 03/17/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: CEMENT FROM 2426' TO 2003' GEL FROM 2003' TO 175', CEMENT FROM 175' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 03/17/2006 12:00 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran tubing and tagged bottom at 2426'. Pumped 60 barrels of gel and 70 sacks of cement with 2 sacks of cottonseed hulls. Cement was placed from 2426' to 1818' and had gel from 1818' to 280'. Pulled the tubing up to 288' and circulated 55 sacks of cement from 288' to surface.

Perfs:

Top	Bot	Thru	Comments
2048	2426		

RECEIVED  
KCC DISTRICT #3  
NOV 20 2006 TH  
CHANUTE, KS

INVOICED  
DATE 12-4-06  
INV. NO. 2007060898

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

RECEIVED Form CP-2/3  
NOV 27 2006  
KCC WICHITA

PKT