

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24266-00-00
Spot: NENWNE Sec/Twnshp/Rge: 27-19S-19E
335 feet from N Section Line, 1683 feet from E Section Line
Lease Name: BUZZARD Well #: 27-31 POW
County: ANDERSON Total Vertical Depth: 1190 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1190		165 SX
SURF	8.625	21		4 SX CMT

\$ 38.68

Well Type: MON UIC Docket No: _____ Date/Time to Plug: 04/27/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: PUMP 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 900'; PUMP 9.5 PPG BENTONITE MUD FROM 900' TO 150'; PUMP 60/40 CLASS A/POZIMIX CEMENT FROM 150' TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 04/27/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

SQUEEZE PLUG WELL. PUMP 75 SACKS OF 60/40 POZ MIX AND SHUT IN AT 1200 PSI.

Perfs:

Top	Bot	Thru	Comments
1133	1135		
1123	1125		
1119	1121		
1114	1117		
1107	1110		

RECEIVED
KCC DISTRICT #3

NOV 20 2006 FG

CHANUTE, KS

INVOICED
DATE 12-4-06
INV. NO. 2007060901

Remarks: OPERATER PLUGGED WELL.

Plugged through: TBG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 27 2006
KCC WICHITA

PCT