

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00009-00-00
Spot: SWSENE Sec/Twnshp/Rge: 6-14S-19W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: LV IRVIN Well #: 1
County: ELLIS Total Vertical Depth: 3883 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3878	0	w/unknown sxs cmt
SURF	8.625	192	0	W/100 SXS CMT \$ 126.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2006 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEVIN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel and 800# hulls.
Casing leak at 1615' - 1677'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2006 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 2150' - 1550' - 810' - 240'.
TIH with tubing to 2500' - mixed and pumped 180 sxs with 500# hulls.
Pulled up to 1000' - circulated cement with 40 sxs and 200# hulls.
POOH. Swaged onto 5 1/2" and circulated cement up 8 5/8" with 40 sxs.
Hole full of cement.

Perfs:


Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

INVOICED
DATE 12-4-06
INV. NO. 2007060902

District: 04

Signed



(TECHNICIAN)

ND

RECEIVED

Form CP-2/3

NOV 30 2006

KCC WICHITA

NOV 29 2006

PKT

BRUNSON & RAY FLEMING, JR. #1 L.V. IRVIN 6-14-19W 35
 SW SE NE


Contr. PAM-KAR DRILLING COMPANY ELLIS County

E 2269RB Comm. Comp. 6-27-52 IP EST 72 BOPD

Tops	Depth	Datum
HEEB	3516	-1247
LANS	3560	-1291
CONG	3850	-1581
SIMP	3871	-1602
SIMP SND	3875	-1606
T D	3883	-1615

Casing
 8" 192 DP 3883: 1410' OIL/8
 5" 3878 HRS

IRVIN POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS