

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20650-00-00
Spot: NWSESESW Sec/Twnshp/Rge: 22-29S-41W
600 feet from S Section Line, 2180 feet from W Section Line
Lease Name: SANTA FE Well #: 22-2
County: STANTON Total Vertical Depth: 5865 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: ATTN: REGULATORY GROUP PO BO
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	40		3.5 YDS.
PROD	5.5	5817		1150 SX \$ 190.61
SURF	8.625	1647		700 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/09/2006 3:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: ROGER NORTHCUTT Company: _____ Phone: (620) 492-1435

Proposed Plugging Method: MIX & PUMP 300# HULLS & 25 SX CMT, DISPLACE TO BOTTOM WITH MUD, PRESSURE & SI. PULL STRETCH ON CASING & SHOOT OFF AT 1577'. LOAD HOLE WITH MUD & PUMP 50 SX CMT AT 1577'. POOH WITH CASING TO 600', LOAD HOLE, MIX & PUMP 30 SX CMT. POOH TO 40', LOAD HOLE, MIX & PUMP 10 SX CMT TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 11/10/2006 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

MIX & PUMP 300# HULLS & 25 SX CMT, DISPLACE TO BOTTOM WITH MUD, PRESSURE & SI. PULL STRETCH ON CASING & SHOOT OFF AT 1577'. LOAD HOLE WITH MUD & PUMP 50 SX CMT AT 1577'. POOH WITH CASING TO 600', LOAD HOLE, MIX & PUMP 30 SX CMT. POOH TO 40', LOAD HOLE, MIX & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5397	5472		OPEN

INVOICED
DATE 12-4-06
INV. NO. 2007060890

Remarks: USED COMMON BY SARGENT & HORTON. RECOVERED 1577' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland PART III
(TECHNICIAN)

RECEIVED
NOV 29 2006
KCC WICHITA

Form CP-2/3

PGT