

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-24229-00-00  
Spot: NENW Sec/Twnshp/Rge: 27-19S-19E  
800 feet from N Section Line, 1850 feet from W Section Line  
Lease Name: PEINE TRUST Well #: 27-21  
County: ANDERSON Total Vertical Depth: 1225 feet

Operator License No.: 33138  
Op Name: MERITAGE KCM EXPLORATION, LLC  
Address: INDEPENDENCE PLAZA 1050 17TH ST  
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1213		165 SXS CMT
SURF	8.625	22		4 SXS CMT
T1	2.875	1149		

\$ 39.81

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2006 8:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: LARRY BRYANT Company: \_\_\_\_\_ Phone: (670) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBDT TO 700';  
CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 700' TO 4' BELOW GROUND LEVEL; CUT CASING AND  
WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 04/27/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 60/40 POZ MIX TO SURFACE. PULL TUBING AND TOP OFF WELL. PUMP 120 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1116	1118		
1112	1114		
1105	1108		
1074	1076		
943	945		
917	919		
892	894		
878	880		
870	872		
849	851		
834	836		

RECEIVED  
KCC DISTRICT #3

NOV 20 2006 FG

CHANUTE, KS

INVOICED  
DATE 12-4-06  
INV. NO. 2007060901

Remarks: OPERATER PLUGGED WELL.

Plugged through: TBG

District: 03

Signed Frank Guilfoyle  
(TECHNICIAN)

RECEIVED  
NOV 27 2006  
KCC WICHITA

Form CP-2/3

PKT