

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24230-00-00
Spot: SESW Sec/Twnshp/Rge: 27-19S-19E
660 feet from S Section Line, 1750 feet from W Section Line
Lease Name: ROCKERS Well #: 27-24
County: ANDERSON Total Vertical Depth: 1190 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1184		165 SXS CMT
SURF	8.625	22		4 SXS CMT
T1	2.875	1140		

\$ 38.68

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/06/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBDT TO 700';
CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 700' TO 4' BELOW GROUND LEVEL; CUT CASING AND
WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 06/06/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING AND TOP OFF WELL. PUMP TOTAL OF 112 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1103	1105		
1098	1100		
1092	1094		
1058	1059		
1030	1032		
1017	1019		
876	878		
862	864		
835	837		
820	822		

RECEIVED
KCC DISTRICT #3

NOV 20 2006 FG

CHANUTE, KS

INVOICED
DATE 12-4-06
INV. NO. 2007060901

Remarks: OPERATER PLUGGED WELL.

Plugged through: TBG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

RECEIVED
Form CP-2/3
NOV 27 2006
KCC WICHITA

PK