

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24233-00-00
Spot: NENW Sec/Twnshp/Rge: 35-19S-19E
660 feet from N Section Line, 1800 feet from W Section Line
Lease Name: ROCKERS Well #: 35-21
County: ANDERSON Total Vertical Depth: 1186 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-------------|
| PROD | 54.5 | 1174 | | 165 SXS CMT |
| SURF | 8.625 | 22 | | 4 SXS CMT |
| T1 | 2.875 | 1147 | | |

\$ 38.55

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/24/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 700';
CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 700' TO 4' BELOW GROUND LEVEL; CUT CASING AND
WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 05/24/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 114 SACKS OF 60/40 POZ MIX. PULL TUBING AND TOP OFF WELL. PUMP TOTAL OF 124 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1121 | 1124 | | |
| 1106 | 1108 | | |
| 1101 | 1103 | | |
| 1094 | 1097 | | |
| 1060 | 1062 | | |
| 1049 | 1051 | | |
| 1038 | 1040 | | |
| 888 | 890 | | |
| 873 | 875 | | |
| 867 | 869 | | |
| 845 | 847 | | |
| 831 | 833 | | |

RECEIVED
KCC DISTRICT #3

NOV 20 2006 FG

CHANUTE, KS

INVOICED
DATE 12-4-06
INV. NO. 2007060901

Remarks: OPERATER PLUGGED WELL.

Plugged through: TBG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

RECEIVED
NOV 27 2006
KCC WICHITA

Form CP-2/3

PKT