

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24235-00-00
Spot: SWSE Sec/Twnshp/Rge: 26-19S-19E
800 feet from S Section Line, 1550 feet from E Section Line
Lease Name: GRETENCORD Well #: 26-34
County: ANDERSON Total Vertical Depth: 1235 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1224		165 SX CMT
SURF	8.625	22		4 SX CMT

\$ 40.14

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/07/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LARRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 700';
CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 700' TO 4' BELOW GROUND LEVEL; CUT CASING AND
WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 06/07/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING AND TOP OFF WELL. PUMP TOTAL OF 163 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1158	1160		
1151	1153		
1145	1147		
933	935		
913	915		
904	906		
889	891		
881	883		
859	861		
844	846		

RECEIVED
KCC DISTRICT #3

NOV 20 2006

CHANUTE, KS

FG

INVOICED

DATE 12-4-06
INV. NO. 2007060901

Remarks: OPERATER PLUGGED WELL.

Plugged through: TBG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

RECEIVED_{orm CP-2/3}
NOV 27 2006
KCC WICHITA

PKT