

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24239-00-00
Spot: SESW Sec/Twnshp/Rge: 22-19S-19E
760 feet from S Section Line, 1900 feet from W Section Line
Lease Name: PERKINS Well #: 22-24
County: ANDERSON Total Vertical Depth: 1220 feet

Operator License No.: 33138
Op Name: MERITAGE KCM EXPLORATION, LLC
Address: INDEPENDENCE PLAZA 1050 17TH ST
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1211		165 SX CMT
SURF	8.625	22		4 SX CMT

\$ 39.65

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/24/2006 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: LSRRY BRYANT Company: _____ Phone: (970) 301-1411

Proposed Plugging Method: CIRCULATE 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SAX COTTON SEE HULLS FROM PBTD TO 700';
CIRCULATE 60/40 CLASS A/POZIMIX CEMENT FROM 700' TO 4' BELOW GROUND LEVEL; CUT CASING AND
WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 05/24/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

RUN TUBING TO TD. PUMP 60/40 POZ MIX FROM TD TO SURFACE. PULL TUBING AND TOP OFF WELL. PUMP TOTAL OF 114 SACKS OF POZ MIX. WELL PLUGGED.

Perfs:

Top	Bot	Thru	Comments
1143	1145		
1137	1140		
1131	1134		
1097	1099		
1082	1084		
932	934		
907	909		
894	896		
863	865		
848	850		

RECEIVED
KCC DISTRICT #3

NOV 20 2006 FG

CHANUTE, KS

INVOICED
DATE 12-4-06
INV. NO. 2007060901

Remarks: OPERATER PLUGGED WELL.

Plugged through: TBG

District: 03

Signed Frank Guilfoyle
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 27 2006
KCC WICHITA

PKT