

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-24265-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 26-19S-19E  
338 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: KUESER Well #: 26-31 POW  
County: ANDERSON Total Vertical Depth: 1230 feet

Operator License No.: 33138  
Op Name: MERITAGE KCM EXPLORATION, LLC  
Address: INDEPENDENCE PLAZA 1050 17TH ST  
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1222		165 SX CMT
SURF	8.625	22		4 SX CMT

**\$ 39.98**

Well Type: MON UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/05/2006 8:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: LARRY BRYANT Company: \_\_\_\_\_ Phone: (970) 301-1411

Proposed Plugging Method: PUMP 60/40 CLASS A/POZIMIX CEMENT WITH 0.5 SACKS COTTON SEED HULLS FROM PBTD TO 900'; PUMP 9.5 PPG BENTONITE MUD FROM 900' TO 150'; PUMP 60/40 CLASS A/POZIMIX CEMENT FROM 150' TO 4' BELOW GROUND LEVEL; CUT CASING AND WELD STEEL PLATE 4' BELOW GROUND LEVEL; GRADE SURFACE LEVEL.

Plugging Proposal Received By: DAVID P. WILLIAMS WitnessType: NONE  
Date/Time Plugging Completed: 06/05/2006 12:00 AM KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:

PUMP 71 SACKS OF 60/40 POZ MIX INTO CASING AT 500 PSI. SHUT IN CASING.

Perfs:

Top	Bot	Thru	Comments
1131	1133		
1126	1128		
1118	1122		

RECEIVED  
KCC DISTRICT #3

NOV 20 2006 FG

CHANUTE, KS

**INVOICED**  
DATE 12-4-06  
INV. NO. 2007060901

Remarks: OPERATER PLUGGED WELL.

Plugged through: CSG

District: 03

Signed Frank Guilfoyle  
(TECHNICIAN)

RECEIVED  
Form CP-2/3  
NOV 27 2006  
KCC WICHITA

PCT