

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-19447-00-00
Spot: NENENE Sec/Twnshp/Rge: 3-25S-17E
4970 feet from S Section Line, 166 feet from E Section Line
Lease Name: PIQUA GAS STORAGE Well #: 0-8
County: WOODSON percep Total Vertical Depth: 389 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HIGHWAY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.178	347		56
SURF	8	17		

\$ 35.00

Well Type: GSO UIC Docket No: _____ Date/Time to Plug: 11/03/2006 8:00 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING & ROUST SVS, INC.
Proposal Rcvd. from: BERNI ROCKERS Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO T.D. PLUG SOLID WITH CLASS A CEMENT. CUT CASING 4 BELOW SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2006 2:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

THIS WELL CONSISTED OF 5 1/2" CASING TO 347' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. 1" PIPE WAS RAN INTO THE 5 1/2" CASING TO 375'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. THE 5 1/2" CASING WAS THEN SQUEEZED TO 700 PSI AND SHUT IN.

RECEIVED
KCC DISTRICT #3

NOV 15 2006

CHANUTE, KS

INVOICED
DATE 12-4-06
INV. NO. 2007060905

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED

NOV 27 2006

KCC WICHITA

Form CP-2/3

PKP