

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

September 27, 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Elmer Zimmerman of Woodman-Iannitti Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Woodman-Iannitti Drilling Co.

Complete Address: 104 South Broadway, Ste 1008, Wichita, Kansas 67202

Lease Name: Angel Well No. 1

Location: 100' South + 30' E. of NW SE SE Sec. 33 Twp. 10 Rge. 15 (E) (W)

County: Osborne Total Depth: 2891'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Zimmerman was instructed to plug the well as follows:

Anhydrite top 1030' Elev. 1932 KB.
Circulate hole and fill with mud. Pump 50 sacks cement through
drill pipe at 850'. Pump 50 sacks cement through drill pipe
at 250'. Fill hole with mud to 40'. Push plug and 1/2 sack
balls to 40' and cap hole with 10 sacks cement. Cement rat hole
with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

10-5-82
OCT 05 1982

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

[Signature]
Conservation Division Agent