

15-141-20124-00-00

FORM CP-2

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

November 24, 1981

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Don Armbruster of Pioneer Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Liberty Enterprises, Inc.

Complete Address: 308 W. Mill, Plainville, Kansas 67663

Lease Name: Hachmeister "B" Well No. 1

Location: NE SE NE Sec. 31 Twp. 10 Rge. 15 (E) (W)

County: Osborne Total Depth: 3555'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Armbruster was instructed to plug the well as follows:

8 5/8" - 206' - 135 sacks cement 2% gel - 3% c.c.

Circulate hole and fill with mud. Pump 70 sacks cement through

drill pipe at 870'. Pump 40 sacks cement through drill pipe

at 200'. Fill hole with mud to 40'. Push plug and 1/2 sack

balls to 40' and cap hole with 10 sacks cement. Cement rethole

with 5 sacks cement.

orders by M. Schmidt

Very truly yours,

Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
11-30-81  
NOV 30 1981  
CONSERVATION DIVISION  
Wichita, Kansas