



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor  
MARION BEATTY Chairman  
HARRY G. WILES Commissioner  
RICHARD C. BYRD Commissioner  
RAYMOND B. HARVEY Secretary  
CLYDE E. MILLIGAN Counsel

15-105-00006-00-00

Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date March 22, 1959, authorized the following plugging operation:

Operator's Full Name: Brunson-Spines, Inc.

Complete Address: 302 Union Center, Wichita, Kansas

Lease Name: Pruitt Well No. 1

Location: SW-NE-SW Sec. 8 Twp. 10 Rge. 7 (E) (W) X

County: Lincoln Total Depth: 3695

Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 500' with heavy mud--  
push plug and 1/4 sack hulls to 500' and cement with 20 sacks thru drill  
pipe. Fill hole to 235' with heavy mud--push plug and 1/4 sack hulls  
to 235'--cement with 20 sacks thru drill pipe. Fill hole to 40' with  
heavy mud--push plug and 1/4 sack hulls to 40'--cement with 10 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 1959  
04-01-1959  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

Signed: [Signature]  
Conservation Division Agent