

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20, 121-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Rains and Williamson Oil Company, Inc.

Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name Kuelling Well No. 1

Location SE SE SE Sec. 25 Twp. 10 Rge. 15 (~~East~~) (West)

County Osborne Total Depth 3570'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A X

Other well as hereinafter indicated     

Plugging Contractor Operator and Halliburton Co.

Address      License No.     

Operation Completed: Hour: 12:45 AM Day: 22 Month: February Year: 1982

Plugging Operations attended by Agent?: All X Part      None     

The above well was plugged as follows: Top Anhydrite 990' Elev. 1826 KB

Hole circulated and Filled with mud. 50 sacks cement pumped through drill pipe at 930'. 50 sacks cement pumped through drill pipe at 300'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement.

Cement used: 50/50 Pozmix w/2% gel. and 3% c.c.

Amount of Surface Casing: 8 5/8" - 250' - 135 sacks 60/40 Pozmix w/2% gel and 3% c.c.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: *William J. Lomen*  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INDEXED

DATE 3-5-82  
INV. NO. 9580-W

RECEIVED  
STATE CORPORATION COMMISSION  
Conservation Division Agent

2-24-82  
FEB 24 1982

CONSERVATION DIVISION  
Wichita Kansas