

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

Received
6-26-78
JUN 26 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 141-20,040 -00-00 (of this well)

Operator's Full Name Isern Petroleum Co.

Complete Address Box 436 Ellinwood, Kansas 67526

Lease Name Bartlett Well No. 1

Location NE SE SW Sec. 29 Twp. 10 Rge. 15 (E) (W) X

County Osborne Total Depth 3676'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Inc. & Allied Cementing Co.

Address RR # 2 Victoria, Kansas License No.

Operation Completed: Hour 3:00 PM Day 24 Month 6 Year 1978

The above well was plugged as follows:

- Filled hole with mud and spotted 50 sx cement at 500'.
- Filled hole with mud and spotted 25 sx cement at 240'.
- Filled hole with mud to 40' and 1/2 sx hulls, plug, and
- 10 sx cement to bottom of celler.
- 2 sx cement in rat hole.
- 257' of 3 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Duan Rankin
Well Plugging Supervisor

DATE 6-26-78
INV. NO. 7550-2