

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20, 145-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Woodman-Lannith Drilling Co.

Complete Address 104 South Broadway, Ste 1008, Wichita, Kansas 67202

Lease Name Angel Well No. 1

Location 100'S. and 30'E of NW SE SE Sec. 33 Twp. 10 Rge. 15 (East)(West)

County Osborne Total Depth 2891

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools and Sun Oilwell Cementing

Address \_\_\_\_\_ License No. 24

Operation Completed: Hour: 10:45 AM Day: 28 Month: September Year: 19

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

Anhydrite top 1030' Elev. 1932KB.  
Hole circulated and Filled with mud. 50 sacks cement pumped  
through drill pipe at 850'. 50 sacks cement pumped through  
drill pipe at 250'. Hole Filled with mud to 40'. Plug and 1/2  
sack hulls pushed to 40' and hole cemented to base of  
cellar with 10 sacks cement. Rathole cemented with 10  
sacks cement.

Amount of Surface Casing: 8 5/8" - 245' - 160 sacks

I hereby certify that the above plugging instructions were given as herein stated.

Signed: \_\_\_\_\_  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Working on Lost Hole 5-24-4 w. Reno Co.

RECEIVED  
STATE CORPORATION COMMISSION  
10-5-82  
OCT 05 1982

Signed: [Signature]  
Conservation Division Agent

INVOICED

CONSERVATION DIVISION  
Wichita Kansas

DATE 10-20-82

NO. 1469-W