

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

RECEIVED

DEC 16 2004

KCC WICHITA

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-091-22848-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Osborn Energy, L.L.C. KCC LICENSE # 32294  
(owner/company name) (operator's)

ADDRESS 24850 Farley Street CITY Bucyrus

STATE KS ZIP CODE 66013 CONTACT PHONE # (913) 533-9900

LEASE Stuart WELL# 1 SEC. 35 T. 14 R. 24 (East/West)

Apx. SW SW NW SPOT LOCATION/0000 COUNTY Johnson

3060 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)

370 FEET (in exact footage) FROM E(W) (circle one) LINE OF SECTION (NOT Lease Line)

(SIGW)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 20' CEMENTED WITH 5 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 1085 CEMENTED WITH 142 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4 shots/ft. 463' - 466'

ELEVATION 993 T.D. 1260 PBDT 1085 ANHYDRITE DEPTH None  
G.L. (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK No JUNK IN HOLE No

PROPOSED METHOD OF PLUGGING (As per Frank Guilfoyle w/ K.C.C.) 50' cement plug on bottom.

Gel spacer to 500'. Cement from 500' to 413' (50' above top perf). Gel spacer to 300'.

Cement from 300' to surface. (12/06/2004)

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rex R. Ashlock PHONE# ( ) (913) 533-9900

ADDRESS 24850 Farley Street For Osborn Energy, L.L.C. City/State Bucyrus, KS 66013

PLUGGING CONTRACTOR Company Tools KCC LICENSE # 32294

ADDRESS 24850 Farley, Bucyrus, KS 66013 (company name) (contractor's) PHONE # ( ) (913) 533-9900

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Sometime during December of 2004.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12/06/2004 AUTHORIZED OPERATOR/AGENT: Rex R. Ashlock (signature) For Osborn Energy, L.L.C.

Consolidated Industrial Services, Inc. (Lic. #31440), will cement well for Osborn Energy, L.L.C.

SCANNED

WELL DRILLERS LOGGING REPORT

THICKNESS FORMATION TOTAL DEPTH COMMENTS

20	Surface	20	
18	Lime	38	
26	Shale	64	
9	Lime	73	
14	Shale	87	SANDY
3	Red Bed	90	
2	Shale	92	
1	Red Bed	93	
11	Shale	104	
5	Lime	109	
40	Shale	149	
2	Lime	151	Damp
10	Shale	161	
3	Lime	164	
1	Shale	165	
20	Lime	185	
1	Shale	186	
1	Blk. Slate	187	gas (tested)
7	Shale	194	
20	Lime	214	
1	Shale	215	
1	Blk. Slate	216	gas (tested)
1	Shale	217	
18	Lime	235	Hertha
10	Shale	345	
8	Sand	353	gas (tested)
17	Shale	370	
5	Red Bed	375	
35	Shale	410	
4	Red Bed	414	
5	Shale	419	
5	Lime	424	
5	Shale	429	
1	Blk. Slate	430	gas (tested)
5	Shale	435	
7	Lime	442	
3	Shale	445	
5	Sand	450	

RECEIVED  
DEC 16 2004  
KCC WICHITA

PAGE # 1

RECEIVED  
KCC DISTRICT #3

DEC 10 2004

CHANUTE, KS

~~Stewart #1~~  
Stuart #1  
35-14-24E

WELL DRILLERS LOGGING REPORT

THICKNESS FORMATION TOTAL DEPTH COMMENTS

14	Ohale	4104	
2	Blk Slate	4106	
12	Ohale	478	
1	Lime	479	
2	Ohale	481	
4	Lime	485	
3	Ohale	488	
5	Red Bed	493	
14	Ohale	507	
1	Blk Slate	508	tested & gas
28	Ohale	536	
4	Sand	540	tested & gas
72	Ohale	612	
1	Coal	613	
37	Ohale	650	
2	Blk Slate	652	
43	Ohale	695	
1	Coal	696	
19	Ohale	715	
10	Ohale (fine)	725	
5	Sand	730	
20	Ohale	750	
10	Ohale (sway)	760	
17	Ohale	777	
5	Sand	782	white-water
70	Ohale	852	
7	Sand	860	
35	Ohale	895	
5	Lime	900	
15	Hardlime	915	
100	Lime	1015	
2	Lime *SOFT	1017	SOFT - break - water
98	Lime	1115	
8	Ohale	1123	
80	Lime	1203	
7	Lime SOFT	1210	
50	Lime	1260	T.O. 1260

RECEIVED  
DEC 16 2003  
KCC WICHITA

RECEIVED  
KCC DISTRICT #3

PAGE #2

Stewart #1

DEC 10 2004

CHANUTE, KS

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Osborn Energy, L.L.C.  
24850 Farley  
Bucyruss, KS 66013

December 16, 2004

Re: STUART #1  
API 15-091-22848-00-00 01  
SWSWNW 35-14S-24E, 3060 FSL 370 FWL  
JOHNSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #3  
1500 W. 7th  
Chanute, KS 67220  
(620) 432-2300