

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Jason Oil Company, LLC
Address: P.O. Box 701, Russell, KS 67665
Phone: (785) 483-8027 Operator License #: 33813
Type of Well: Oil Docket #:
The plugging proposal was approved on: by: Hubert Deines
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

API Number: 15-167-37872-00-00
Lease Name: Bond B per CP 2/3
Well Number: B-1 KCC PKT 11-17-06
Spot Location (QQQQ): G SWSESW
328 328 Feet from North / South Section Line
1980 3433 Feet from East / West Section Line
Sec. 23 Twp. 14 S. R. 13 East West
County: Russell
Date Well Completed: 11-13-03 3/5/1940
Plugging Commenced: 7-6-06
Plugging Completed: 7-12-06


per GPS Ftg's
per RBDMS

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 5 1/2, 3224, 0.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. Moved pumping unit with backhoe, unhooked well head, pulled rods, changed over for tubing, pulled 76 joints tubing, shot holes at 1350', 875', 150', ran tubing back down to 1500', swedge in, pumped 200 sacks, 5# hulls at 1500', pulled tubing out, tied on to 5 1/2" casing, pumped 70 sacks, had 500 psi max, shut in 300 psi, cut 5 1/2" casing off 4' below ground

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 401 W Main, Lyons, KS 67554
Name of Party Responsible for Plugging Fees: Jason Oil Company, LLC
State of KANSAS County: Russell ss.
James L. Schoenberger (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) James L. Schoenberger
(Address) P. O. Box 701, Russell, KS 67665-0701
November 14th day of 2006
My Commission Expires: July 18, 2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED NOV 16 2006 KCC WICHITA