


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Osborne County, Sec. 22 Twp. 10 Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Icer Addis
Lease Name Bessey Well No. 1
Office Address Box 27 Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed May 2, 1958
Application for plugging filed May 10, 1958
Application for plugging approved May 2, 1958
Plugging commenced May 2, 1958
Plugging completed " " "
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation none Depth to top Bottom Total Depth of Well 3398 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug was set at 200' with 1/4 sack of hulls and 25 sacks of cement, top plug was set at 40' with 1/4 sack of hulls and 10 sacks of cement. Finished plugging hole at 5 pm on May 2, 1958.

5-14-58

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Triangle Drilling, Inc.
Address Box 287 Russell, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Donald D. Vaughan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald D. Vaughan
Donald D. Vaughan Box 619 Great Bend, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of May 19 58
My commission expires April 29, 1961
Dean E. Cooley Notary Public

PLUGGING
FILE SEC 22 T 10 R 15W
BOOK PAGE 100 LINE 25

WELL LOG

COMPANY
CONTRACTOR
FARM
LOCATION

Icer Addis
Triangle Drilling, Inc.
#1 Bessy
NE NE NW of Section 22-10-15W
Osborne County, Kansas

ELEVATION
SURFACE PIPE

1833 KB
8 5/8" cemented at 213' w/140 sacks common
with 1 sack gel and 2% c.c.

PRODUCTION
COMMENCED
COMPLETED

D & A
April 22, 1958
May 2, 1958

FORMATION	DEPTH
Surface clay and sand	40
Sandstone, shale and shells	90
Shale and shells	480
Hard sandstone	550
Shale and sandstone	590
Red bed, sandstone and shale	1018
Anhydrite	1053
Shale and shells	1575
Limestone and shale	1910
Limestone	2000
Limestone and shale	2723
Limestone	3385
Sand and Conglomerate	3398

FORMATION TOPS

Anhydrite	1018	(- 815)	driller's
Topoka	2723	(- 890)	
Hoebner	2967	(-1132)	
Toronto	2988	(-1155)	
Lansing	3016	(-1183)	
Sand Conglomerate	3385	(-1552)	
RTD	3398	(-1565)	

5-14-58
CONSERVATION DIVISION
Wichita, Kansas

A E E I R A V I I

STATE OF KANSAS, COUNTY OF BARTON, SS.

I, Donald D. Vaughan, of the TRIANGLE DRILLING, INC., being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Donald D. Vaughan
Donald D. Vaughan

Subscribed and sworn to before me this 12th day of May, 1958.

Wesley E. Roebuck
Notary Public

My commission expires: April 29, 1961.

PLUGGING
FILE SEC. 22 T. 10 R. 15W
BOOK PAGE 100 LINE 25