

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-21,295-00-00

LEASE NAME Lanoung

WELL NUMBERR B-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1650 Ftt. from S Section Line

3630 Ftt. from E Section Line

SEC. 29 TWP. 9 RGE. 17 (E) or (W)

COUNTY Rooks

LEASE OPERATOR Leo Hammerschmidt

ADDRESS P.O. Box 426 Plainville, Ks 67663

PHONE# (785)-434- OPERATORS LICENSE NO. 31670

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well (Completed) \_\_\_\_\_

Plugging Coomenced 8-12-2000

Plugging Coompleted 8-12-2000

The plugging proposal was approved on 8-12-2000 (date)

by Herb Deinos (KCC District Agent's Name).

Is ACO-1 filed? N.A. If not, is well log attached? N.A.

Producing Formation K.C. Depth to Top 3414 Bottom 3538 T.D. 3640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Surface line	-	0	241	8 1/8"	241	none
Prod. Cas.	-	0	3638	4 1/2"	3638	none

SEP 13 2000  
9-13-2000

CONSERVATION DIVISION  
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Perforated tubing & casing at 3200' & pumped 100 sq cmt. & displaced to 1100'. Shot tubing off @ 1100'. Prod. 60 sq cmt. w/ 500# balls in cmt. to circ @ surf in prod. Cas. Pulled 1106' Tbg. Tied onto prod. cas. & pumped 25 sq cmt. w/ MAX P.S.I. 0600# S.I. 200# Tied onto produced (8 1/2") S.I. and pumped 400 sq cmt.

Name of Plugging Contractor Leo Hammerschmidt License No. 31670

Address P.O. Box 426 Plainville, Ks 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Leo Hammerschmidt


STATE OF Kansas COUNTY OF Rooks, sis.

Leo Hammerschmidt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Leo Hammerschmidt


(Address) P.O. Box 426

SUBSCRIBED AND SWORN TO before me this 11 day of Sept, 2000, 19 2000



Michelle R. Haas  
Notary Public

My Commission Expires: 10/04/03



WOODMAN & IANNITTI DRLG. CO. #1 GANOUNG "B" 29-9-17W  
 1008 DOUGLAS BLDG SW NE SW  
 WICHITA, KS 67202  
 CONTR JOHN O. FARMER, INC. CTY ROOKS

GEOL \_\_\_\_\_ FIELD GANOUNG

E 2137 KB CM 5/23/81 CARD ISSUED 8/6/81 IP P 10 BOPD, TR WTR  
 LANS 3414-3538 OA

+	+	+
+	+	+
+	+	+

API 15-163-21,295

SMP	TOPS	DEPTH	DATUM
ANH		1420	+ 717
TOP		3056	- 919
HEEB		3271	-1134
TOR		3292	-1155
LANS		3314	-1177
BKC		3542	-1405
CONG CHT		3558	-1421
SIMP		3616	-1479
ARB		3637	-1500
RTD		3640	-1503

8 5/8" 241/175sx; 4 1/2" 3638/150sx  
 DST (1) 3267-3327/30-30-30-30,  
 REC 10' OIL SPKD M, SIP 130-81#  
 FP 65-65/65-65#  
 DST (2) 3461-3541/30-30-30-30, REC  
 70' M W/FEW SPKS OIL, SIP 1070-  
 1070#, FP 102-142#

(OVER)

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

WOODMAN & IANNITTI DRLG CO. #1 GANOUNG "B" 29-9-17W  
 SW NE SW

MICT - CO, PF 3566-3568 & 3562-3564  
 AC750G, SWB 8GFPH W/TR OIL/4HRS, PF 3536-3538 & 3519-3522  
 SET BP @ 3556, AC1500G, SWB 30GFPH (30% OIL)/3HRS, PF 1/  
 3477, 1/3479, 1/3459, SET RBP @ 3497, AC2000G, SWB 3 1/2 BFPH  
 (20% OIL)/7HRS, PF 3414-3416, AC1000G, SWB 15GFPH (SSO)/  
 5HRS, POP

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 13 2000

CONSERVATION DIVISION  
 Wichita, Kansas