

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rooks SEC. 29 TWP. 9 RGE. 17  W  
Location as in quarters or footage from lines:  
SW/SW/SE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Woodman-Iannitti Drilling Company  
Lease Name Ganoung "C" Well No. #1  
Office Address Box 308 - Great Bend, Ks. 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): D&A  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced February 19, 1982  
Plugging completed March 1, 1982  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3637'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	245'	NONE
				4 1/2"	3634'	1853.83'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Pushed plug to 3010'  
Dumped fifty feet (50') sand and four (4) sacks cement.  
Shot pipe @ 2500', 2300', 2000' and 1800'.  
Pulled forty-seven (47) joints of 4 1/2" casing.  
Squeezed well with five (5) sacks hulls, fifteen (15) sacks gel  
one hundred forty (140) sacks 50/50 pozmix cement with 4% added  
gel and 3% calcium chloride.

RECEIVED  
MAR 11 1982  
3-11-82  
CONSERVATION DIVISION  
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
James W. Rockhold  
Box 698 - Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 10<sup>th</sup> day of Mar, 1982



Ruth Brack  
Notary Public.

My Commission expires: \_\_\_\_\_