


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

ROOKS County. Sec. 29 Twp. 9S Rge. 17W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner K & E and OIL TRADING
Lease Name REMPE Well No. 1
Office Address 719 Union Center Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 21st, 1957 19
Application for plugging filed August 20th, 1957 19
Application for plugging approved August 20th, 1957 19
Plugging commenced August 20th, 1957 19
Plugging completed August 20th, 1957 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3635 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill with heavy mud to 600' and set plug, run 20 sacks cement through drill pipe. Fill with heavy mud to 230' and set plug, run 20 sacks cement through drill pipe. Fill with mud to 40' and run 1/2 sack hulls and set solid bridge with 10 sacks of cement to cellar floor. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.
Address 719 Union Center Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
Dale Silcott, K & E DRILLING, INC.
719 Union Center Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 1957

Patricia M. Edwards, Notary Public.

My commission expires August 11th, 1958

PLUGGING
FILE SEC. 29 T. 9 R. 17W
BOOK PAGE 39 LINE 27

8-28-57

Conservation Division
State Corporation Commission
Wichita, Kansas

W E L L L O G

OPERATOR: K & E and OIL TRADING
719 Union Center Building
Wichita, Kansas

FARM NAME: #1 REMPE

CONTRACTOR: K & E DRILLING, INC.
719 Union Center Building
Wichita 2, Kansas

LOCATION: SW SW SE
Section 29-98-17W
Rooks County, Kansas

CASING: 8-5/8" @ 245' (160 sx)

COMMENCE: 8-13-57
COMPLETE: 8-21-57
8-20-57

R.T.D. 3635'

ELEVATION: 2133' KB

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Surface soil & Clay	35
Shale	245
Shale	620
Shale & Sand	990
Sand	1140
Shale & Shells	1420
Anhydrite	1460
Shale & Shells	1545
Shale & Shells	1865
Lime & Shale	2150
Shale & Lime	2550
Lime & Shale	2795
Shale & Lime	3050
Lime	3515
Lime & Shale	3555
Conglomerate, Shale & Chert	3580
Lime	3535
R.T.D.	3535

CERTIFICATION

STATE OF KANSAS }
 } SS:
COUNTY OF SEDGWICK }

I, Dale Silcott of the K & E DRILLING, INC. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 REMPE well.

Dale Silcott
Dale Silcott

Subscribed and sworn to before me this 26th day of August 1957.

Patricia M. Edwards
Patricia M. Edwards, Notary Public

My commission expires: August 11, 1958.

PLUGGING
FILE SEC 29 T 9 R 17W
BOOK PAGE 39 LINE 27

8-28-57

10W