


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 30 Twp. 9S Rge. 17 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Osage Oil & Gas Co. & C-G Drilling Co.  
Lease Name Workman Well No. 1  
Office Address 107 Rule Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 23 19 56  
Application for plugging filed August 23 19 56  
Application for plugging approved August 23 19 56  
Plugging commenced August 24 19 56  
Plugging completed August 24 19 56  
Reason for abandonment of well or producing formation Too low structurally



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3595 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	184'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 179'. Set plug. Put in 1/2 sack Hulls and 15 sacks of cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack Hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.  
Address 107 Rule building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway  
107 Rule Building  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 1956

My commission expires March 22, 1960

Celeste B. Romine  
Notary Public.

PLUGGING  
FILE SEC. 30 T. 9 R. 17W  
BOOK PAGE 93 LINE 24

8-28-56

CONTRACTOR'S WELL LOG

OPERATOR OSAGE OIL & GAS COMPANY & C-G DRILLING CO. WELL NAME WORKMAN #1

LOCATION SE SE SW SECTION 30-9S-17W RIG NO. 1

COUNTY ROOKS STATE KANSAS

COMMENCEMENT DATE AUGUST 14, 1956 COMPLETION DATE AUGUST 23, 1956

LOG OF WELL

Elevation 2116 rotary bushing.  
All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	185	Surface Soil		
185	910	Sand-Shale		
910	1070	Sand		
1070	1405	Red Bed		
1405	1445	Anhydrite		
1445	1600	Lime-Shale		
1600	2030	Lime-Shale		
2030	2160	Lime-Shale		
2160	2310	Lime-Shale		
2310	2480	Lime-Shale		
2480	2590	Lime-Shale	0° - 2500	
2590	2750	Lime-Shale	0° - 2750	
2750	2910	Lime-Shale		
2910	3000	Lime-Shale	0° - 3000	
3000	3090	Lime-Shale		
3090	3160	Lime-Shale		
3160	3226	Lime-Shale		
3226	3290	Lime-Shale	0° - 3250	DST 3262-3278
3290	3305	Lime-Shale		DST 3286-3305
3305	3390	Lime-Shale		
3390	3429	Lime-Shale		DST 3332-3395
3429	3490	Lime-Shale		DST 3395-3429
3490	3535	Lime-Shale	0° - 3500	
3535	3595	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Set 184' (9 jts) 8-5/8" OD Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK ) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
G. F. Galloway

Subscribed and sworn to before me this 27th day of August, 1956

My commission expires:  
March 22, 1960

Celste B. Romine  
Celste B. Romine Notary Public  
Romine

**PLUGGING**  
FILE SEC 30 T 9 R 17W  
BOOK PAGE 93 LINE 24

**RECEIVED**  
STATE COMMISSION  
CONSERVATION DIVISION  
Kansas