

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01440-00-00
Spot: NESWSE Sec/Twnshp/Rge: 18-9S-21W *
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SUTOR B Well #: 7
County: GRAHAM Total Vertical Depth: 3846 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	1783		75 SX
PROD	5.5	3843	0	w/unknown sxs cmt
SURF	8.625	165	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2006 2:30 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Squeezed at 900' - 1000' - 1300' - 1390'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2006 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 225 sxs cement with 500# hulls.
Max. P.S.I. 800#. S.I.P. 500#.
Hooked onto 4 1/2" x 5 1/2" annulus - instant pressure and 5 1/2" x 8 5/8" annulus - instant pressure.
08/10/2006 - WLTD 1039' - no fluid in the hole. Topped off well with 55 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3843	3846		OPEN HOLE

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

RECEIVED
Form CP-2/3
DEC 6 11 2006
KCC WICHITA