

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22265-00-00
Spot: NESENW Sec/Twnshp/Rge: 30-9S-17W
150 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: PLAINVILLE PUBLIC LIBR Well Number: 1
County: ROOKS Total Vertical Depth: 3676 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

Production Casing Size: 4.5 feet: 3656 150 SX CMT
Surface Casing Size: 8.625 feet: 215 135 SX CMT

11947

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/15/2003 10:00 AM

Plug Co. License No.: 8925 Plug Co. Name: LIBERTY OPER & COMPL, INC

Proposal Rcvd. from: ROGER COMEAU Company: LIBERTY OPER & COMPL, INC Phone: (785) 434-4686

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid Level 2200'. PBTB 3641'.
Production Perfs 3601' - 3604'; 3565' - 3578'.
Squeeze surface to 1450' with 350 sxs cement.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/15/2003 12:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Hooked up to backside - pressured instant 1000#.
Hooked up to 4 1/2" casing. Allied pumped 185 sxs cement with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.

RECEIVED
OCT 23 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 10-23-03

INV. NO. 2004060669


OCT 15 2003

LIBERTY OPERATIONS & COMPLETIONS
 308 W. MILL #1 PLAINVILLE PUBLIC LIBRARY 30-9-17W
 PLAINVILLE, KS 67663 NE SE NW

CONTR PIONEER DRILLING CO. CTY ROOKS

GEOLOGICAL FIELD WC(1/4 N OF GANOUNG;
 SEP BY DRY HOLES)

ELV 2135 KB SPD 1/20/84 CARD ISSUED 3/15/84 IP P 25 BOPD, NW
2130 GL CONG 3565-3604 OA



1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100

LOG	Tops	Depth/Datum	
			API 15-163-22,265
			8 5/8 " 215 / 135SX; 4 1/2 " 3656 / 150SX
ANH	1463+	672	DST (1) 3537-3590 (ARB) / 30-60-30-30, REC 140' MCO, SIP
TOP	3063-	928	949-848#, FP 50-58 / 67-92#
HEEB	3276-	1141	MICT - CO, PF (PENN CONG) 3601-3604. & 3565-3578, AC 250G
TOR	3296-	1161	(15%), SWB DWN, SO, RE-AC 1500G (15%), SWB DWN, SO, RE-
LKC	3316-	1181	AC 2500G (15%), SWB DWN, SO, POP, P 25 BOPD, NW, 2/17/84
BKC	3544-	1409	
CONG		NOT AVAILABLE	
ARB		3638-	1503
RTD		3676-	1541

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS