

4-061233

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-21,295-00-00

SW NE SW /4 SEC. 29, 09 S, 17 W
1650 feet from S section line
3630 feet from E section line

Operator license# 31670

8/12

Lease: Ganoung Well # B-1

Operator: Leo Hammerschmidt

County: Rooks 118.30

Address: P.O. Box 426
Plainville, Kansas 67663

Well total depth 3640 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 241 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Randy's Well Service License# 31287

Address: P.O. Box 373 - Plainville, Kansas 67663

Company to plug at: Hour: 10:00 A.M. Day: 12 Month: August Year: 2000

Plugging proposal received from: Randy's Well Service

Company: Randy's Well Service Phone: 785-434-2190

Were: Order 240 sxs 60/40 pozmix - 10% gel and hulls.
Emergency permission to plug with rig over hole.

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 2000

8-22-2000

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour 2:00 P.M., Day: 12, Month: August, Year: 2000

Actual plugging report: 8 5/8" set to 241' w/175 sxs. 4 1/2" to 3638' w/150 sxs.
Tubing stuck with packer in the hole. Apparently packer sanded in. Perforated tubing and casing at 2200' and pumped 100 sxs cement and displaced to 1100'. Shot off tubing at 1100'. Pumped 60 sxs cement with 500# hulls with cement to surface in production casing. Pulled tubing. Tied onto 8 5/8" annulus and pumped 40 sxs cement. Pressured to 400#. Tied onto production casing and pumped 25 sxs cement with Max. P.S.I. 600#. S.I.P. 200#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD
Bottom plug(in place): YES , CALC , NO
Plugged through TUBING , CASING
Anhy.plug: YES NO
Dakota plug: YES NO
Elevation: 2132 GL

I did[] / did not[] observe the plugging.

INVOICED

DATE 8/24/00

INV. NO. 200060519

[Signature]
(agent)

Form CP-2/3

[Signature]