

6 010197

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22454-00-00

NW, SEC. 30, T 9 S, R 17 W

_____ feet from N/S section line

_____ feet from W/E section line

Lease Name Plainville Public Library Well # 2

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

County Rooks

Operator: Liberty Opp. & Comp.

Well Total Depth 3680 119.60 feet

Name & Address 308 W. Mill

Conductor Pipe: Size _____ feet

Plainville KS. 67663

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drilg. Co. License Number 5665

Address Same

Company to plug at: Hour: 2 AM Day: 1 Month: 9 Year: 19 84

Plugging proposal received from Tom Alm.

(company name) Pioneer Drilg. (phone) _____

were: order 210 ex. cement 50/50 pozmix 6% gel. 3% C.C.

1.5x hulls 1.8 5/8 plug 1.5x flow seal.

Heavy mud between all plugs.

Pump lim. down drill pipe.

Elev - 2132 Anhydrite 1454-86 Arbuckle 3633

Dakota 1550 Plugging Proposal Received by Walef Balthazor

582 = 880

Plugging Operations attended by Agent?: All _____ Part (None)

Operations Completed: Hour: 8:30 AM Day: 1 Month: 9 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3640 for 30 mi.

25 5x @ 3640

25 5x @ 1470

100 5x @ 880 mixed with 15x flow seal.

40 5x @ 230 Dumped 15x hulls. Pushed plug to 40'

10 5x @ 40

Remarks: 10 5x. in Bat Hole - cementing w. Allied

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-18-84

INV. NO. 3733

RECEIVED

STATE CORPORATION COMMISSION

9-10-84

SEP 10 1984

Signed Walef Balthazor

(TECHNICIAN)

SH
SEP 7
24