

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23567-00-00
Spot: SWSESE Sec/Twnshp/Rge: 18-6S-20W
330 feet from S Section Line, 950 feet from E Section Line
Lease Name: HICKS Well #: 1
County: ROOKS Total Vertical Depth: 3810 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	218		

\$ 123.83

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/14/2006 4:05 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: DUSTY RHOADES Company: BLACK DIAMOND, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 11/17/2006 12:45 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st. Plug at 3725' w/25 sxs.
2nd. Plug at 1870' w/25 sxs.
3rd. Plug at 1145' w/100 sxs.
4th. Plug at 270' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher
(TECHNICIAN)

INVOICED
DATE 12-7-06
INV. NO. 2007060913

NOV 30 2006

RECEIVED
DEC 05 2006
KCC WICHITA

Form CP-2/3