

15-163-01514-00-00

4-041951

1-14

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 7-10-63

C W2 W2 NE /4 SEC. 13 , 09 S, 17 W
1320 feet from N section line
2310 feet from E section line

Operator license# 30553

Lease: Mary Daugherty Well # 7

Operator: Unrein Oil Company

County: Rooks 113,10

Address: 2207 Downing Street
Hays, Kansas 67601

Well total depth 3480 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 203 Feet
W/100 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Unrein Oil Company License# 30553

Address: 2207 Downing Street - Hays, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day: 14 Month: January Year 1998

Plugging proposal received from: Charlie Farr

Company: Unrein Oil Company Phone: 785-628-3530

Were: 4 1/2" casing set at 3465' w/125 sxs cement. Perfs at 3148' - 3381'
Anhy at 1290' - Dakota at 700'.
Ordered 250 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 600# hulls.

RECEIVED
1998 JAN 22 PM 12:17
Dennis L. Hamel

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 12:30 P.M., Day: 14, Month: January, Year: 1998

Actual plugging report: R.U. Cementers to 4 1/2" casing. Squeezed 200 sxs 60/40 pozmix with 10% gel in cement plus 500# hulls down casing. Max. P.S.I. 400#. S.I.P. 200#. R.U. Cementers to 8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls. Max. P.S.I. 300#. S.I.P. 300#.

Remarks: Cemented by Allied Cement Company.

Condition of casing(in hole): GOOD BAD X

Bottom plug(in place): YES X, CALC, NO

Plugged through TUBING CASING X

Anhy.plug: YES X NO

Dakota plug: YES X, NO

Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 1-23-98

INV. NO. 49982