

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03199-00-01
Spot: SESESE Sec/Twnshp/Rge: 5-8S-17W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: ECKERT Well #: 5
County: ROOKS Total Vertical Depth: 3390 feet

Operator License No.: 31171
Op Name: CONTINENTAL OPERATING CO.
Address: 1221 MCKINNEY - SUITE 3700
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	514	514	w/unknown sxs cement
SURF	8.625	103	0	w/unknown sxs cmt

\$ 110.18

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2006 9:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: RALPH BRUNGARDT Company: CONTINENTAL OPERATING COM Phone: (785) 735-4645

Proposed 10/11/2006 - Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plugging 11/20/2006 - Ordered out 90 sxs 60/40 pozmix - 10% gel.
Method: Unable to get below 2290' - decided to P/A.
Anhy 1278' - 1322'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2006 9:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

10/11/2006 - Ran tubing to 1850'.
Allied pumped 40 sxs 60/40 pozmix - 10% gel with 100# hulls.
Pulled tubing to 1322'. Allied pumped 235 sxs cement with 400# hulls - circulated lite cement with hulls.
PTOH. Will run wireline and tag cement. Tagged cement at 220'.
11/20/2006 - Allied pumped 45 sxs 60/40 pozmix - 10% gel. Hole full

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 12/7/06
INV. NO: 2007060914

NOV 28 2006

RECEIVED
DEC 01 2006
KCC WICHITA

CONTINENTAL OPERATING CO
HOUSTON TX 77010

5-08S-17W
SE SE SE

#5 ECKERT OWWO

site: 3 S & 1-1/2 E OF STOCKTON KS
contr: WESTERN WELL SVCG

cty: ROOKS
field: LONE STAR

API 15-163-03199

fr date 03/07/2006
spc date 03/23/2006
orig comp 03/24/2006
card issued 10/09/2006
last revised 10/09/2006

ELV: 1948 KB, 1941 GL LOG
topsdepth/datum
ARB3380 -1434
RTD OLD3394 -1448

IP status

J & A, ARB, 03/25/2006

OLD INFO: OPERATOR WAS V. D. SIDNEY OIL CO, 5
ECKERT, SPD 06/03/1954, 06/13/1954 8-5/8" 103 (ALT 2), 5-1/2"
3381, OIL, P 93 BO & 20 BWPD, ARB 3381-3394,
10/08/1954 (CARD ISSUED 10/15/1954)
CONTR: SIDNEY OIL CO, V. D.
COMMENT: WAS TEMP API IOG-27277
NO CORES OR DSTS
MICT - CO TO 3394, (ARB OH), AC 1000 GAL, SWB DWN,
GSO, POP, IPP 93 BOPD & 18% W, 10/8/1954 (WELL P & A
7/13/1963; REC 1025' OF 5-1/2" CSG)

COPYRIGHT 2006
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

CONTINENTAL OPERATING CO
HOUSTON TX 77010

5-08S-17W
SE SE SE

#5 ECKERT OWWO

NEW INFO: FR 03/07/2006, RE-ENTERED 03/23/2006 WSH DWN TO 1871, NO LOG RUN DC 03/24/2006
COMMENT: KCC API 15-163-03199-0001
TRGT ZN: ARB (OIL), PTD 3390 (ARB), JUNK IN HOLE, COULD NOT REACH BTM, J & A 3/25/2006.