

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20066-00-01

Spot: NESE

Sec/Twnshp/Rge: 16-25S-29W

1980 feet from S Section Line, 660 feet from E Section Line

Lease Name: DAVIDSON

Well #: 1

County: GRAY

Total Vertical Depth: 5206 feet

Operator License No.: 9228

Op Name: MARLIN OIL CORPORATION

Address: PO BOX 14630

OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

CIBP		2900		
------	--	------	--	--

PROD	5.5	4790	649	135 SX CMT
------	-----	------	-----	------------

SURF	8.625	409		325 SX CMT
------	-------	-----	--	------------

\$169.20

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/11/2006 11:45 AM

Plug Co. License No.: 33338

Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: DICK LYNN

Company:

Phone: (405) 818-8738

Proposed Plugging Method: SET CIBP @ 2900' AND CAP W/2 SX CMT. CUT OFF CSG AS DEEP AS POSSIBLE. PLACE 75 SX CMT PLUG FROM 459' TO 359' AND A 10 SX CMT PLUG FROM 34-4'. WELD ON ID COVER PLATE.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: NONE

Date/Time Plugging Completed: 10/11/2006 12:10 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TUBING TO 3000', PUMPED 50 SX CMT AT 100# HULLS. RAN TUBING INTO 1850'. PUMPED 50 SX CMT 1000' AT 100 SX 4% CC. NO CIRCULATION ON EITHER 1850' OR 1000' PLUGS. TAGGED CEMENT AT 504'. 459' AT 50 SX 40' AT 10 SX. HOLE STAYED FULL. TOP PLUGS NOT WITNESSED.

Perfs:

Top	Bot	Thru	Comments
4707	4711		

INVOICED

DATE 12-7-06

INV. NO. 2007060924

Remarks: USED 60/40 POZMIX 6% GEL

Plugged through: TBG

District: 01

Signed Eric MacLaren

(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 29 2006

KCC WICHITA

PT