

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02885-00-02
Spot: NESWSE Sec/Twnshp/Rge: 25-13S-20W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: YOUNGER Well #: 6
County: ELLIS Total Vertical Depth: 3690 feet

Operator License No.: 30680
Op Name: GEIST, WILLIAM DBA GEIST OIL OPER
Address: 807 GRANT RR 2
VICTORIA, KS 67671

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	3562		175 SXS
PROD	5.5	3804	0	w/unknown sxs cmt
SURF	8.625	250	0	w/unknown sxs cmt

\$119.93

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/27/2006 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BILL GEIST Company: GEIST OIL OPERATIONS Phone: (785) 735-7020

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 11/27/2006 10:20 AM

WitnessType: COMPLETE (100%)
KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto backside and pressured up to 600#.
Full of cement.
Tied onto 4 1/2" and pumped 190 sxs cement with 600# hulls.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3628	3646		
3580	3602		

INVOICED
DATE 12-7-06
INV. NO. 2007060917

Remarks: ALLIED CEMENTING COMPANY-TICKET #33437.

Plugged through: CSG

District: 04

Signed

Marvin Mills

(TECHNICIAN)

NOV 29 2006

RECEIVED

DEC 01 2006

KCC WICHITA

15-051-02885-00-00 25-13-20W
 LARIO OIL & GAS COMPANY #6 YOUNGER NE SW SE

Contr. PRIME DRLG 990 FSL 1650 FEL ELLIS County

E 2157 Comm. 2-21-58 Comp. 5-2-58 IP 3000 BOPD, NW

Tops	Depth	Datum	Casing
ANH	1450	707	8" 240
TOP	3142	-985	5" 3802
HEEB	3397	-1240	DST 3518-40/1 HR, 285' MDY
TOR	3418	-1261	SW, BHP 520#
LANS	3438	-1281	DST 3800-04/1 HR, 200' GIP,
			134' CL 0, 30' MDY 0, BHP
MARM	3729	-1572	1130#
CONG	3758	-1601	CO TD: ACID 250: SWB 15 BOPH/
			4 HR
ARB	3800	-1643	IRVIN POOL
TD	3804	-1647	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

-	+	-	+
+	+	+	+
+	+	+	+
+	+	+	+

E23,056