

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23034-00-01

Spot: NWSWSWNW

Sec/Twnshp/Rge: 20-19S-13W

3270 feet from S Section Line,

200 feet from W Section Line

Lease Name: WILLIAMS OWWO

Well #: 1

County: BARTON

Total Vertical Depth: 3461 feet

Operator License No.: 6170

Op Name: GLOBE OPERATING, INC.

Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3536	0	150 SX
SURF	8.625	763	0	275 SX

\$ 112.48

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/01/2006 8:30 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: RICHARD STALCUP

Company: GLOBE OPERATING, INC.

Phone: (620) 792-7607

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/01/2006 10:15 AM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3250' - dumped 5 sxs cement - no stretch.
Cut casing at 1600'.
Ran tubing to 1550'.
Pumped 100 sxs 60/40 pozmix - 10% gel cement.
Pulled to 800' - circulated with 100 sxs cement.
POOH. Tied onto casing.
Pumped 150 sxs cement - circulated up backside.

Perfs:

Top	Bot	Thru	Comments
3475	3478		
3338	3344		
3303	3308		

INVOICED

DATE 12-7-06

INV. NO. 2007060918

Remarks: COPELAND CEMENTING.

Plugged through: CSG

District: 04

Signed

Case Morris

(TECHNICIAN)

RECEIVED

Form CP-2/3

DEC 05 2006

KCC WICHITA

NOV 30 2006

PKT

L. D. DRILLING, INC. RT. #1, BOX 183-B GREAT BEND, KS 67530
 #1 WILLIAMS "OWWO" COMPANY TOOLS
 20-19-13W 2010' FNL & 200' FWL, NW/4
 CONTR CTRY BARTON
 GEOL FIELD GREAT BEND TWST
 ELV 1857 KB SPD 3/5/84 CARD ISSUED 4/5/84 IP P 20 80 & 20 BWPD
 LKC 3303-3364 OA
 ARB 3461-3478 OA

LOG	Tops	Depth/Datum
ANH		756 + 1101
*B/ANH		779 - 1078
TOP		2764 - 907
HEEB		3066 - 1209
TOR		3082 - 1225
DOUG		3096 - 1239
BR LM		3164 - 1307
LANS		3177 - 1320
BKC		3394 - 1537
CONG		3403 - 1546
*ARB		3455 - 1598
ORTD		3461 - 1604
DDTD		3537 - 1680
*SAMPLE TOPS		

API 15-009-23,034-A

OLD INFO: OPERATOR WAS BILL WITCRAFT, #1 WILLIAMS, SPD 3/1/83, SET 8 5/8 " 763 / 385 SX, COMP. AS D & A: ARB, 3/7, 83. (CARD ISSUED 5/26/83), CONTR: WOODMAN & IANNITTI, GEOL: RICHARD M. FOLEY
 DST (1) 3180-3240 (LKC) / 30-30-30-30, 285' GIP, REC 15' M, W/TR OIL IN TOOL, SIP 121-140#, FP 54-54 / 65-65#
 DST (2) 3280-3315 (LKC) / 30-45-60-45, 1200' GIP, REC 120' THIN SOCM (15% OIL, 10% WTR, 75% MUD), 60' DARK GRAY OIL & GCWM (25% OIL, 20% WTR, 55% MUD), 120' THIN SO & GCWM (10% OIL, 70% WTR, 20% MUD), SIP 745-701#, FP 43-65 / 91-129#
 DST (3) 3317-3355 (LKC) / 30-30-60-45, 2500' GIP, REC 45' OIL & GCM (11% OIL, 89% MUD), 60' BRN OIL & GCM (50% OIL, 8% WTR, 42% MUD), 100' DARK GRAY HO & GCM (53% OIL, 5% WTR, 42% MUD), 20' MDY OIL (71% OIL, 4% WTR, 25% MUD), SIP 474-463# FP 43-54 / 65-75#
 (over)

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

L. D. DRILLING, INC. #1 WILLIAMS "OWWO" 20-19-13W 2010' FNL & 200' FWL, NW/4

DST (4) 3359-3390 (LKC) / 30-45-60-45, 500' GIP, REC 30' HO & GCM & MDY OIL, 60' MDY GSY OIL, 60' BLK MDY OIL & GAS EMUL, SIP 509-147#, FP 43-54 / 54-75#
 DST (5) 3393-3461 (ARB) / 30-30-60-30, 420' GIP, REC 70' BLK MDY OIL & GAS EMUL, 120' MDY WTR, SIP 1069-1047#, FP 65-86 / 107-151#

NOTE: CORRECTION: 2/17/83 - ORIGINALLY FIRST REPORTED IN 20-19-14W

NEW INFO: FR 3/7/84, RE-ENTERED 3/5/84, WSH DWN TO ORTD, DD 3537 TD, SET 5 1/2 " 3536/150SX; MICT - CO, PF (ARB) 3475-78 W/2 SPF, AC 300G (MOD-202), SWB DWN, SO, PF (ARB) 3461-63 W/2 SPF, AC 300G (MOD-202), SWB DWN, SO, PF (LKC) 3361-64 W/2 SPF, AC 100G (28% NE), SWB DWN, SO, PF (LKC) 3338-44 W/2 SPF, AC 1500G, SWB DWN, SO, PF (LKC) 3303-08 W/2 SPF, AC 1500G (28%), SWB DWN, SO, POP, P 20 BO & 20 BWPD, 3/16/84 - COMMINGLED