

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20150-00-00
Spot: N2SESE Sec/Twshp/Rge: 6-14S-19W
990 feet from S Section Line, 660 feet from E Section Line
Lease Name: IRVIN B Well #: 5
County: ELLIS Total Vertical Depth: 3885 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3881	0	125 SX
SURF	8.625	200	0	150 SX

\$ 126.26

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/28/2006 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEVIN AXELSON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-1314

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 600# hulls.
Perf Tech perfed at 2142' - 1562' - 750' - 250'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/28/2006 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2502'. Rigged to tubing and pumped 200 sxs with 400# hulls mixed in.
Pulled tubing to 1000'. Rigged to tubing - pumped 65 sxs with 200# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing - pumped 35 sxs cement - circulated out of 8 5/8" backside - shut in 8 5/8".
Pressured with 200# P.S.I.
Blew small hole on top of head. No shut in pressure.

Perfs:

Top	Bot	Thru	Comments
3881	3885		ARBUCKLE

INVOICED
DATE 12-7-06
INV. NO. 2007060925

Remarks: QUALITY OIL WELL SERVICE-TICKET #1277.

Plugged through: TBG

District: 04

Signed [Signature]

(TECHNICIAN)

RECEIVED

Form CP-2/3

DEC 05 2006

KCC WICHITA

NOV 29 2006

PT

RALPH R. RHYNE #5 IRVIN 6-14-19W
 N/2 SE SE
 Contr. SHIELDS DRUG CO Cty. ELLIS
 Geol. R. P. NIXON Pool IRWIN
 E. 2246 KB Cm. 10/26/67 Cp. 1/18/68 IPP 25 BOPD + 80%W
 ARB 3881-85
 AP. 15 051 20,150

LOG Tops	Depth	Datum	Csg. 8" 200, 5" 3881/125 sx
TOP	3236	+990	
HEEB	3490	-1244	CO 3885 TD, A 1250 GALS
TOR	3515	-1269	
LANS	3531	-1285	
CONG	3821	-1575	
ARB	3880	-1634	
ID	3885	-1639	

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS