

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1978
7-12-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Oden of Red Tiger Drlg. Co. has this date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Corp.

Complete Address: P. O. Box 247, Wichita, Kansas

Lease Name: Beck Well No. 1-20

Location: 1065' FSL 255' FWL NW Sec. 20 Twp. 10 Rge. 15 (B) (W) X

County: Osborne Total Depth 3600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oden was instructed to plug the well as follows:

Fill hole with mud and spot 50 sx cement at 540'.

Fill hole with mud and spot 25 sx cement at 240'.

Fill hole with mud to 40' & 1/2 sx hulls, plug, & 10 sx cem.

2 sx cement in rat hole.

277' of 3 5/8" surface casing cement circ.

Very truly yours,

David Rankin
Conservation Division Agent