

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163-21, 075 00-00 (of this well)

Operator's Full Name FRONTIER OIL COMPANY.
Complete Address 1720 HANS. ST. BKT. TRUST BLDG. WICHITA, KS. 67202
Lease Name GARVERT Well No. #1
Location SW-SW-SE Sec. 30 Twp. 9 Rge. 17 (E) (W)
County ROOKS Total Depth 3633 FE
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated _____

Plugging Contractor RED TIGER DRILLING (RIG 2)
Address 1720 N-S. BKT. TRUST BLDG. - WICHITA, KS. License No. _____

Operation Completed: Hour 9:30 AM Day 6th Month JUNE Year 1980

The above well was plugged as follows:

8 5/8" 286 FE SP. CUC. w/ 180ST COMMON 2% GEL. - 3% CA.-CL.
ORDERED 105ST 50/50 Pozmix 6% GEL. + 8 5/8" PLUG. (ENV. 2117)
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG. @ 440 FE w/ 40ST CMT.
2ND PLUG. @ 240 FE w/ 20ST CMT.
3RD PLUG. - SOLID BRIDGE HULLS + PLUG @ 40^{FE} to 0 w/ 10ST CMT.
5TH IN RAT HOLE

CEMENTED BY APPLIED OILS

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 6-13-80
INV. NO. 2357-W

Signed: Marion Schmidt
Well Plugging Supervisor

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
JUN 13 1980