

15-163-20680-00-00

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2/18/77
FEB 18 1977
CONSERVATION DIVISION
Kansas
(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,680

Operator's Full Name Edmiston Oil Co.

Complete Address 800 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name KEAS Well No. 1

Location SE NW SW Sec. 13 Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3593'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 9 P Day 16 Month 2 Year 1977

The above well was plugged as follows:
RTD 3593' 8 5/8 csg set 293' cwc 175 sx. Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 2-18-77

INV. NO. 4659-W