


15-163-00064-00-00
WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Rooks County. Sec. 15 Twp. 9 Rge. 17 (E) W (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 330' from South, 330' from east
Lease Owner Phillips Petroleum Company NW/4
Lease Name Mary Well No. 1
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 19, 19 42
Application for plugging filed March 19, 19 42
Application for plugging approved March 19, 19 42
Plugging commenced March 19, 19 42
Plugging completed March 19, 19 42
Reason for abandonment of well or producing formation No commercial production zone encountered. Dry hole.
If a producing well is abandoned, date of last production ** 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C.T. Alexander
Producing formation Arbuckle Lime Depth to top 3536' Bottom 3648' Total Depth of Well 3648' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Rotary hole - no oil or gas commercial producing horizons encountered.</u>				<u>8-5/8"</u>	<u>1310</u>	<u>None-cement to surface</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Cemented hole from TD. 3648' to 3633'. Mud laden fluid from 3633' to 1310', 10 sacks cement from 1310' to 1280'. Mud laden fluid from 1280' to 37'. 10 sacks cement from 37' to 0'.

PLUGGING
FILED 15-9-17W
BOOK PAGE 28 LINE 16

Received
3/26/42
MAR 26 1942
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Mr. F.W. Shelton,
Address Box 779, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
F.W. Shelton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F.W. Shelton

Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25 day of March 19 42

NOTARY PUBLIC
My commission expires My Commission Expires Dec. 20, 1944

Lloyd B. Bannum
Notary Public.

Formation Record

Lease **Mary**
(Sec. 15-9-18, Rooks County, Kansas)Well No. **1**

FROM	TO	Formation	REMARKS
0	220	Shale and shells	
220	610	Shale, lime, and shells	
610	660	Sand & shale	
660	810	Gray shale & clay	
810	885	Sand, shells, and shale	
885	900	Shale	
900	1035	Sand	
1035	1148	Shale and shells	
1148	1310	Shale and shells	
1310	1380	Anhydrite	Top anhydrite 1310'
1380	1645	Shale and Red Bed	
1645	1975	Shale & shells	
1975	2020	Shale & lime shells	
2020	2141	Shale and shells	
2141	2449	Shale and lime	
2449	2730	Shale, lime & shells	
2730	3003	Shale, lime & shells	
3003	3116	Shale and lime	
3116	3150	lime & Chert	
3150	3280	Lime, chert, shale	Top K.C. 3182'
3280	3319	Shale & lime	
3319	3327	Lime	Core 3318-26' 7' recovery
3327	3366	Lime, shale & chert	
3366	3500	Chert, lime & shale	
3500	3536	Chert, lime, & shale	Base K.C. 3456'. Top Conglom. 3492' Top Simpson 3530'. Top Arb. 3536'.
3536	3548	Arbuckle Lime	Ran Schlumberger - good porosity - no shows. Dry and Abandoned
T.D.	3648		

