

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.
Address: 250 N. Water, Suite 300
Phone: (316) 267-3241 Operator License #: 30606
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/16/06 (Date)
by: Barry Metz Pat Staab *KCC PRT per CP 2/3* (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3881 Bottom: 3885 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-20150-0000
Lease Name: Irvin B
Well Number: #5
Spot Location (QQQQ): 9908 *nw N2* - SE - SE *Per OPS Flgs*
9908 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 6 Twp. 14 S. R. 19W East West
County: Ellis
Date Well Completed: 11/16/07 *1/18/08 Per RBDMS PRT*
Plugging Commenced: 11/28/06
Plugging Completed: 11/28/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	200	8 5/8	200	0
	Production	Surface	3881	5 1/2	3881	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


RU Quality Oilwell Cementing: Mixed 200 sx 60/40 Poz w/10% gel and 400# hulls @ 2502'. Pulled 48 jts tubing. Mixed 65 sx 60/40 Poz w/10% gel and 200# hulls @ 1025'. Gained circ from 8 5/8" w/cement to surface. Pulled remaining 33 jts of tubing. Swedged into 5 1/2" csg. Mixed 35 sx 60/40 Poz w/10% gel and press to 700 psi. Small leak in 5 1/2" near slip area. SI csg w/ 200 psi. Plug job witnessed & approved by Pat Staab with KCC, Hays.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606
Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.
State of Kansas County, Sedgwick, ss.

Susan Sears, Operations Engineer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Susan Sears
(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 5th day of December, 20 06
Susan Brady My Commission Expires: 11-4-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 07 2006
KCC WICHITA