

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/16/06 (Date)

by: Jay Pfeifer (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)  
Lansing Kansas City Depth to Top: 3590 Bottom: 3757 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-00009-0000

Lease Name: LV Irvin KCC PRT 12/16/06 per CP 2/3

Well Number: #1 CP 2/3

Spot Location (QQQQ): SW - SE - NE -  
2310 Feet from  North /  South Section Line

990 Feet from  East /  West Section Line

Sec. 6 Twp. 14 S. R. 19W  East  West

County: Ellis

Date Well Completed: 6/25/52 per RBDMS per

Plugging Commenced: 11/16/06

Plugging Completed: 11/16/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	192	8 5/8	192	0
	Production	Surface	3877	5 1/2	3877	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Quality Oilwell Cementing: Pumped 400# hulls and 160 sx 60/40 Poz with 10% gel @ 2504'. Fluid @ 8 5/8" surface with 1st plug spotted. Pulled 48 jts. tubing and placed bottom of tbg @ 1018'. Pumped 100# hulls and 40 sx 60/40 Poz with 10% gel @ 1018'. TOH w/remaining 33 jts. tbg. Swedged into 5 1/2" csg. Pumped 40 sx 60/40 Poz with 10% gel and topped off casing. Plug job witnessed & approved by Jay Pfeifer with KCC, Hays.


Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.

State of Kansas County, Sedgwick, ss.

Susan Sears, Operations Engineer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Susan Brady

(Address) 250 N. Water, Suite 300; Wichita, KS 67202

My Appt. Expires SUBSCRIBED and SWORN TO before me this 5th day of December 20 06  
Susan Brady My Commission Expires: 11-4-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
DEC 07 2006

KCC WICHITA