

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: D.R. Lauck Oil Co., Inc. Address: P.O. Box 488 Ellinwood, Ks. 67526 Phone: (620) 564-2013 Operator License #: 5427 Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: by: Steve VanGieson (KCC District Agent's Name) Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-095-21186-00-00 Lease Name: Vanlandingham "A" Well Number: 1 Spot Location (OQQQ): C W/2 NE NW 990 Feet from North / South Section Line 1320 Feet from East / West Section Line Sec. 21 Twp. 30 S. R. 7W East West County: Kingran Date Well Completed: 2/20/82 Per RB DMS Plugging Commenced: 11-13-06 Plugging Completed: 11-16-06

Show depth and thickness of all water, oil and gas formations.

Table with 2 main columns: Oil, Gas or Water Records and Casing Record (Surface Conductor & Production). Rows show formation details like size (8-5/8", 5-1/2"), put in depth (285', 4288'), and pulled out depth (None, 3314').

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. Plugged off bottom with sand to 4150' and 5 sxs cement. Cut casing loose @3314', pulled up to 1100', pumped 35 sxs cement, pulled up to 700', pumped 35 sxs. cement, pulled up to 335' and circulated 85 sxs. cement to surface, Plugging Complete. 60/40 pos, 4% gel.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529 Address: P.O. Box 467 Chase, Kansas 67524 Name of Party Responsible for Plugging Fees: D.R. Lauck Oil Co., Inc. State of Kansas County: Rice

RECEIVED DEC 07 2006 KCC WICHITA


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 4th day of December, 2006

[Signature] Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT