

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mull Drilling Company, Inc.
Address: P.O. Box 2758, Wichita KS, 67201-2758
Phone: (316) 264-6366 Operator License #: 5144
Type of Well: D&A Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Jerry W. Stapleton ^{KCC} _{per CP 213} 12/12/06 (KCC District Agent's Name)
Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 101-21974 -00-00
Lease Name: James Trust
Well Number: 1-24
Spot Location (QQQQ): NE - SE - NW - NE
986 Feet from ☒ North / ☐ South Section Line
1505 Feet from ☒ East / ☐ West Section Line
Sec. 24 Twp. 16 S. R. 29 ☐ East ☒ West
County: Lane
Date Well Completed: 10/23/06
Plugging Commenced: 10/23/06
Plugging Completed: 10/23/06
30 ^{KCC PKT 12/12/06} _{per CP 213}

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	210'	8 5/8"	204'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

50 sx @ 2220', 80 sx @ 1410', 40 sx @ 720', 40 sx @ 240', 20 sx @ 60'.

15 sx rathole. 10 sx mousehole. Total 265 sx, 60/40 Poz, 6% gel, 1/4# floseal per sk.

Reported to Jerry Stapleton @ 4:45 p.m. 10/24/06.

By Allied.


Name of Plugging Contractor: WW Drilling License #: 33575
Address: P.O. Box 307, WaKeeney KS 67672

Name of Party Responsible for Plugging Fees: Mull Drilling Company, Inc.
State of Kansas County, Sedgwick, ss.

Mark A. Shreve, President/COO
(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) P.O. Box 2758 Wichita KS 67201-2758



SUBSCRIBED and SWORN TO before me this 6th day of December, 2006
Tannis L. Tritt My Commission Expires: 3.26.2007
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 07 2006
KCC WICHITA